



Date: February 14, 2023

Subject: MegaFlex UL UPS - Samsung 136S Lithium-ion Runtime charts

Thank you for considering an ABB UPS System with Lithium-ion battery support. The following are runtime charts for ABB MegaFlex UL. Please cross reference the kVA and runtime in your ABB quotation (bill of material) with this table to see the corresponding battery backup string quantity in your quotation.

In addition, separate startup and commissioning line item is required for Lithium-ion solutions to insure safe and proper installation of battery system by ABB Field Services. Please insure there this a specific line item chosen and listed in the solution bill of material.

MegaFlex UPS:

DC junction cabinet required with 5 or more battery strings in parallel to accommodate multiple DC cables prior to UPS landing.

	1 String	2 String	3 String	4 String	5 String	6 String	7 String	8 String
MegaFlex UL	Min BOL	Min BOL	Min BOL	Min BOL	Min BOL	Min BOL	Min BOL	Min BOL
1000	x	x	x	x	6	9	10	12
1100	x	x	x	x	x	7	9	11
1200	x	x	x	x	x	6	9	10
1500	x	x	x	x	x	x	x	7
1600	x	x	x	x	x	x	x	6

To learn more about our ABB UPS offer please visit us at <https://electrification.us.abb.com/>

Doc reference #CHT-UPS-MK-0170

ABB Inc.

5900 Eastport Blvd., Bldg. V
Richmond, VA 23231
Phone: +1 800 238 5000
Fax: +1 804 236 4040
abb.com/ups