

Commissioning of synchronous motors and generators



ABB has been manufacturing motors and generators for more than 100 years. This extensive experience provides a solid basis for the company's commissioning services.

All commissioning is performed by fully trained and certified engineers to ensure that the work is done in a safe and efficient way.

—
ABB engineer
checking operating
data

Commissioning need

Synchronous motors and generators with their associated excitation and control equipment include advanced functionality, requiring specialized commissioning know-how and use of the right equipment.

Commissioning is a crucial part of installation and start-up. When carefully performed according to the correct procedures, commissioning is an investment in availability and reliability over the entire lifetime of the equipment.

In order to achieve reliable and safe operation, commissioning requires both system know-how and system tuning experience.

ABB's certified commissioning engineers have extensive experience in both motor and generator start-ups. Their know-how, combined with full support from our design department, ensures short commissioning times and trouble-free operation.

Scope


ABB's engineers utilize a set of standardized commissioning procedures, progressing systematically from preparation through to completion and hand-over.

Benefits

- Full manufacturer support
- Fully updated documentation and software
- Comprehensive commissioning report
- Maximized availability and reliability
- Extended equipment lifetime

Benefits based on

- Original equipment manufacturer:
 - Unrivalled knowledge of ABB motors and generators
 - Full access to ABB's R&D and design experts
- Certified commissioning engineers:
 - Fully qualified and experienced
 - Safe and effective working practices
- Programming tools and test equipment:
 - Improved personnel safety
 - Reduced commissioning time
 - Compliance with scope requirements



—
ABB synchronous generator

Certified commissioning engineers

ABB is the only service provider able to offer certified commissioning engineers for ABB motors, generators and control panels. The certification process is the customer's guarantee of competence, ensuring the engineer is fully qualified and trained in commissioning the equipment safely and in accordance with manufacturers procedures and requirements.

Preparation

Careful preparation is vital for trouble-free commissioning. A detailed schedule must be agreed between the parties to ensure that the required resources are allocated. To achieve maximum efficiency, every on-site activity is planned by ABB and includes customer-specific preparatory work, including:

- Planning on-site safety
- Preparing documents, required equipment, programming tools, software etc.
- Making travel arrangements

Commissioning procedures

Prior to energizing the control panel, the mechanical and electrical installations are reviewed to verify that all requirements are met. Main actions performed:

- Visual check of motor/generator and main terminal box, including cooling and lubrication system
- Electrical measurements and check of all wiring

When it has been confirmed that the complete system is ready to be energized, the main system integration activities are initiated:

- Testing and calibration of settings
- Protection function verification including DCS communication
- Load run and verification of proper start-up conditions and operation

When tuning is completed and the correct operation is confirmed, the on-site commissioning work is finished and the installation is officially handed over to the customer. The hand-over typically includes a control panel demonstration for the operators.

Commissioning report

When commissioning is completed, the customer receives a comprehensive commissioning report, an updated settings list, connection table and circuit diagrams, and final versions of any modified application software included in the original scope of supply.

The commissioning report includes:

- Actions taken during commissioning
- Data from measurements
- Control panel protection settings
- Summary with recommendations

—
For more information please visit:

new.abb.com/motors-generators/service

—
We reserve the right to make technical changes or modify the contents of this document without prior notice. With regard to purchase orders, the agreed particulars shall prevail. ABB Ltd does not accept any responsibility whatsoever for potential errors or possible lack of information in this document.

—
We reserve all rights in this document and in the subject matter and illustrations contained therein. Any reproduction, disclosure to third parties or utilization of its contents – in whole or in parts – is forbidden without prior written consent of ABB Ltd.
Copyright© 2018 ABB, All rights reserved